



NIRMALA NIKETAN INSTITUTE'S  
**COLLEGE OF HOME SCIENCE,  
NIRMALA NIKETAN**

Affiliated to the University of Mumbai  
NAAC Accredited 'A+' Grade

49, New Marine Lines, Churchgate, Mumbai - 400 020. ☎ 2207 6503 / 2200 7544  
Email: principal@nnchsc.edu.in / office@nnchsc.edu.in Web.: www.nirmalaniketan.com

30<sup>th</sup> July 24

**Sub: Inviting Quotations for renovation (Civil Work) of 2<sup>nd</sup> floor food Lab flooring & converting 2<sup>nd</sup> floor toilet into Disable friendly toilet**

Respected Sir/Madam,

We intend to renovate our 2<sup>nd</sup> floor food Lab flooring and convert 2<sup>nd</sup> floor toilet into Disable friendly toilet. We are looking for **vendors to do the renovation and civil work** with the given specifications. We invite you to send your most competitive quotations for the same.

If your prices and terms are favourable, as per our specifications, we shall consider giving the contract to you for renovating the 2<sup>nd</sup> floor food Lab flooring and converting 2<sup>nd</sup> floor toilet into Disable friendly toilet.

Please provide us the quote for the following detailed below:

SRNO	DESCRIPTION	Qty	Unit
<b>A</b>	<b>Food Lab 2<sup>nd</sup> floor</b>		
1	<b>Vitrified Tile Flooring</b>		
	Providing & fixing approved 24" x 24" size, colour, design and make anti skid vitrified tiles flooring in line, level using 1/2" thk. cement mortar (1:2) on proper bedding and curing complete with matching colour cement jointing. (Basic cost of tile is Rs.100/- per Sft)	625.00	Sft
2	<b>Vitrified tile Skirting</b>		
	Providing & fixing 4" ht. vitrified tile skirting in cement mortar (1:3) in matching colour jointing, curing with 6mm x 6mm groove at skirting top etc.	100.00	Rft
<b>B</b>	<b>Handicap Toilet at 2nd floor.</b>		
<b>I.</b>	<b>Demolition Work</b>		
	<b>(Demolition all the brick wall, flooring, tile etc., and the debris take it out of the college campus)</b>		
1	Demolition of existing 6" thk brick wall	47.00	Sft
2	Removing of existing plumbing work	Job	Job

3	Removing of existing flooring with brick bat	47.00	Sft
4	Removing of existing wall tile dado	198.00	Sft
5	Removing of existing window	2.00	No
<b>SRNO</b>	<b>DESCRIPTION</b>	<b>Qty</b>	<b>Unit</b>
<b>II.</b>	<b>Civil Work</b>		
1	<b>Constructing of 6" thk brick wall</b>	35.00	Sft
	Providing & constructing 6" Thick. brick on edge wall in line and level including cement/ sand mortar (1:3) with neat, flush joints along with proper line level plum etc.,		
2	<b>Cement plaster</b>		
	Providing & applying cement sand faced plaster finish 1:4, average. 3/4" thk in two coats in proper plumb line & level complete with necessary scaffolding and curing.	185.00	Sft
3	Providing and applying chemical waterproofing with brick bat coba	47.00	Sft
4	<b>Providing and fixing vitrified tile flooring</b>	45.00	Sft
	Providing & fixing approved 24" x 24" size, colour, design and make anti skid vitrified tiles flooring in line, level using 1/2" thk. cement mortar (1:2) on proper bedding and curing complete with matching colour cement jointing. (Basic cost of tile is Rs.100/- per Sft)		
4	<b>Providing and fixing vitrified tile wall dado</b>	180.00	Sft
	Providing & fixing in position Wall Tile Dado approved shape, size & colour and pattern in dado truly in plumb upto part or full height of wall with machine cut top edge as per the drawings over cement, plaster Pedilite paste of required consistency to avoid any possibility of hollowness behind the tiles, filling the joints with white cement and matching color pigments including curing, scaffolding etc. complete as per drawing, specifications and as directed by the Engineer-in-Charge.		
5	Providing and fixing Wash basin counter made in marble frame and black granite top	1.00	No
6	Providing and fixing Granite door frame in black granite double data frame	1.00	No
7	Providing and fixing Door in powder coated Aluminium frame and Bakelite panel	1.00	No
8	Providing and fixing Granite Window frame	2.00	No
9	Providing and fixing Aluminum Loured Window	2.00	No
<b>III.</b>	<b>Plumbing Work</b>		
<b>SRNO</b>	<b>DESCRIPTION</b>	<b>Qty</b>	<b>Unit</b>
1	Providing & fixing/testing Internal plumbing/ water / drainage connection with necessary GI/ PVC/Brass/ CP pipes, elbows, valves, T's, nahnhi trapes etc. including best quality 4" dia PVC pipe with saddles, connectors etc. for drainage connecting W.C. commodes to the available drainage outlet at site to be fixed on M.S./ C.I. Brackets.	L.S	L.S
2	WC	1.00	No
3	Wash basin	1.00	No
4	Pillar Cock	1.00	No
5	2 way Angle cock	2.00	No
6	Jet Spray	1.00	No

7	Nhani Trap jali	1.00	No
8	Bottle trap	1.00	No
9	Wall Mounted grab bar for Handikap WC	1.00	No
10	Soap Dispensor	1.00	No
11	Paper Holder	1.00	No
12	Grab Bar	1.00	No

**Material List & Specification of the material**

No	Particular	Company Name
1	Cement	Ambuja or LT
2	Tile 2'0"x2'0"	Kajaria or Equivalent
3	Wash Basin	Sonora, Soncera or Equivalent ISI Make
4	WC	Sonora, Soncera or Equivalent ISI Make
5	Plumbing fitting	Prince, Sicko, Jaquar or Equivalent
6	Aluminum frame	Jindal
7	Paint	Asian Paint

Estimated Cost: Rs 4lakhs.(1.19 +2.6 (including GST)

Kindly also send details on the mode of payment and terms and conditions (if any). Please give the reference of our website on your quotation and address the quotation to **“The Principal, College of Home Science Nirmala Niketan, Mumbai – 400020”**.

Kindly mail the softcopy to [principal@nnchsc.edu.in](mailto:principal@nnchsc.edu.in) and [admin@nnchsc.edu.in](mailto:admin@nnchsc.edu.in) by 3rd Aug 2024, 1 pm, and courier the quotation in a sealed envelope to College of Home Science Nirmala Niketan, 49, New Marine Lines Mumbai 400020, by 3<sup>rd</sup> Aug 2024 by 5 pm.

We hope to hear from you soon regarding this quote request.

We also look forward to a long-standing business relationship with you if this transaction is a success.

Thanking You,

Yours Sincerely,

In Charge Principal

Prof. Dr. Vishaka Karnad

*Vishaka Karnad*  
3/8/2024